

PCT REQUEST

2990533PC/su

Original (for SUBMISSION) - printed on 26.04.2000 01:01:06 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/FI 0 0 / 0 0 3 5 7
0-2	International Filing Date	2 6 APR 2000 (2 6 -04- 2000)
0-3	Name of receiving Office and "PCT International Application"	The Finnish Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request Prepared using	PCT-EASY Version 2.90 (updated 08.03.2000)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	National Board of Patents and Registration (Finland) (RO/FI)
0-7	Applicant's or agent's file reference	2990533PC/su
I	Title of invention	LOCATION MANAGEMENT FOR CELLULAR SYSTEMS
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	NOKIA NETWORKS OY
II-5	Address:	Keilalahdentie 4 FIN-02150 Espoo Finland
II-6	State of nationality	FI
II-7	State of residence	FI
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	RAJANIEMI, Jaakko
III-1-5	Address:	Lapinrinne 2 A 11 FIN-00180 Helsinki Finland
III-1-6	State of nationality	FI
III-1-7	State of residence	FI

PCT REQUEST

Original (for SUBMISSION) - printed on 26.04.2000 01:01:06 PM

III-2	Applicant and/or inventor	applicant and inventor
III-2-1	This person is:	US only
III-2-2	Applicant for	AHMAVAARA, Kalle
III-2-4	Name (LAST, First)	Hakaniemenranta 18 D 62
III-2-5	Address:	FIN-00530 Helsinki
		Finland
III-2-6	State of nationality	FI
III-2-7	State of residence	FI
III-3	Applicant and/or inventor	applicant and inventor
III-3-1	This person is:	US only
III-3-2	Applicant for	EINOLA, Heikki
III-3-4	Name (LAST, First)	Kaksoiskiventie 7-9 B 5
III-3-5	Address:	FIN-02760 Espoo
		Finland
III-3-6	State of nationality	FI
III-3-7	State of residence	FI
III-4	Applicant and/or inventor	applicant and inventor
III-4-1	This person is:	US only
III-4-2	Applicant for	BÄCK, Juha
III-4-4	Name (LAST, First)	Kulosaarenpuistotie 44 B 22
III-4-5	Address:	FIN-00570 Helsinki
		Finland
III-4-6	State of nationality	FI
III-4-7	State of residence	FI
III-5	Applicant and/or inventor	applicant and inventor
III-5-1	This person is:	US only
III-5-2	Applicant for	HULKKONEN, Tony
III-5-4	Name (LAST, First)	Porvoonkatu 1 F 214
III-5-5	Address:	FIN-00510 Helsinki
		Finland
III-5-6	State of nationality	FI
III-5-7	State of residence	FI
III-6	Applicant and/or inventor	applicant and inventor
III-6-1	This person is:	US only
III-6-2	Applicant for	HAUMONT, Serge
III-6-4	Name (LAST, First)	Riistavuorenkuja 3 B 10
III-6-5	Address:	FIN-00320 Helsinki
		Finland
III-6-6	State of nationality	FR
III-6-7	State of residence	FI

PCT REQUEST

2990533PC/su


Original (for SUBMISSION) - printed on 26.04.2000 01:01:06 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	KOLSTER OY AB
IV-1-2	Address:	Iso Roobertinkatu 23 P.O. Box 148 FIN-00121 Helsinki Finland
IV-1-3	Telephone No.	+ 358 9 618 821
IV-1-4	Facsimile No.	+ 358 9 602 244
IV-1-5	e-mail	Kolster@Kolster.Fi
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW SD SL SZ TZ UG ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE CH&LI CY DE DK ES FI FR GB GR IE IT LU MC NL PT SE and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT (patent and utility model) AU AZ BA BB BG BR BY CA CH&LI CN CR CU CZ (patent and utility model) DE (patent and utility model) DK (patent and utility model) DM DZ EE (patent and utility model) ES FI (patent and utility model) GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR (patent and utility model) KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX NO NZ PL PT RO RU SD SE SG SI SK (patent and utility model) SL TJ TM TR TT TZ UA UG US UZ VN YU ZA ZW

PCT REQUEST

2990533PC/su

Original (for SUBMISSION) - printed on 26.04.2000 01:01:06 PM

V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.	
V-6	Exclusion(s) from precautionary designations	NONE
VI-1	Priority claim of earlier national application	
VI-1-1	Filing date	28 June 1999 (28.06.1999)
VI-1-2	Number	991466
VI-1-3	Country	FI
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1
VII-1	International Searching Authority Chosen	Swedish Patent Office (ISA/SE)
VIII	Check list	number of sheets electronic file(s) attached
VIII-1	Request	5 -
VIII-2	Description	10 -
VIII-3	Claims	3 -
VIII-4	Abstract	1 2990533p.txt
VIII-5	Drawings	3 -
VIII-7	TOTAL	22
	Accompanying items	paper document(s) attached electronic file(s) attached
VIII-8	Fee calculation sheet	✓ -
VIII-10	Copy of general power of attorney	✓ -
VIII-16	PCT-EASY diskette	- diskette
VIII-18	Figure of the drawings which should accompany the abstract	3
VIII-19	Language of filing of the international application	English
IX-1	Signature of applicant or agent	 Ralf Syvänen
IX-1-1	Name	KOLSTER OY AB

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	26 APR 2000 (26-04-2000)
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	

PCT REQUEST

2990533PC/su

Original (for SUBMISSION) - printed on 26.04.2000 01:01:06 PM

10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

16.06.2000

RECEIVED

19-06-2000

KOLSTER OY AB

Kolster Oy Ab

Iso Roobertinkatu 23

00120 Helsinki

Patenttihakemus nro: 991466
Luokka: H04Q / JSA
Hakija: Nokia Networks Oy
Asiamies: Kolster Oy Ab
Asiamiehen viite: 2990533FI

Määräpäivä: 16.12.2000

Patenttihakemuksen numero ja luokka on mainittava kirjelmässänne PRH:lle

Suoritetussa tutkimuksessa ei tullut esiin estettä hakemuksen hyväksynnälle. Hakijaa kehoitetaan toimittamaan virastoon englannin kielellä jätetystä hakemuksesta PL 8 § 5 mom mukainen käännös (PA 3 § 1 mom).

Esimerkkinä tutkimuksessa esille tulleista julkaisuista liitetään oheen hakijan aiemmat hakemusjulkaisut WO 99/09774 ja WO 98/32304, joista ensin mainitussa esiintyy yhteyden rakentelu runkoverkosta matkaviestimelle kahden radioverkko-ohjaimen (RNC) kautta (tässä julkaisussa palvelevaa RNC:tä kutsutaan ankkuri RNC:ksi). Jälkimmäinen puolestaan käsittelee reititysalueen (RA) päivitystä kahden pakettiradiverkon (GPRS) palvelusolmun (SGSN) välillä.

Ps. Vaikuttaa siltä, että comprise sana on pudonnut matkasta sivun 4 rivillä 34 ja sivun 12 rivillä 20.

Tutkijainšinoori
Puhelin:

J. Saranka
Jukka Saranka
(09) 6939 5394

Lausumanne huomautusten johdosta on annettava viimeistään yllämainittuna määräpäivänä. Jollette ole antanut lausumanne virastoon viimeistään mainittuna määräpäivänä tai ryhtynyt toimenpiteisiin tässä välipäätöksessä esitettyjen puutteellisuuksien korjaamiseksi, jätetään hakemus sillensä (patenttilain 15 §). Sillensä jätetty hakemus otetaan uudelleen käsiteltäväksi, jos Te neljän kuukauden kuluessa määräpäivästä annatte lausumanne tai ryhdytte toimenpiteisiin esitettyjen puutteellisuuksien korjaamiseksi ja samassa ajassa suoritate vahvistetun maksun, 320 mk hakemuksen ottamisesta uudelleen käsiteltäväksi. Jos lausumanne on annettu virastoon oikeassa ajassa, mutta esitettyjä puutteellisuuksia ei ole siten korjattu, että hakemus voitaisiin hyväksyä, se hylätään, mikäli virastolla ei ole aihetta antaa Teille uutta välipäätöstä (patenttilain 16 §). Uusi keksinnön selitys, siihen tehdyt lisäykset ja uudet patenttivaatimukset on aina jätettävä kahtena kappaleena ja tällöin on otettava huomioon patenttiasetuksen 19 §.

PATENTTI- JA REKISTERIHALLITUS

Patentti- ja innovaatiolinja

TUTKIMUSRAPORTTI

PATENTTIHAKEMUS NRO	LÜOKITUS
991466	H04Q 7/38

TUTKITTU AINEISTO
Patenttijulkaisukokoelma (FI, SE, NO, DK, DE, CH, EP, WO, GB, US), tutkitut luokat
Tiedonhaut ja muu aineisto
Haku Epodoc ja WPI tietokannoissa termeillä: RNC or radio network controller or routing area. Haku Epodoc tietokannassa termillä location luokassa h04q7/38r+/ec

VIITEJULKAISUT		
Kategoria*)	Julkaisun tunnistetiedot	Koskee vaatimuksia
A	WO 99/09774 lk H04Q 7/38, Nokia Telecommunications Oy	
A	WO 98/32304 lk H04Q 7/38, Nokia Telecommunications Oy	
<p>*) X Patentoitavuuden kannalta merkittävä julkaisu yksinään tarkasteltuna Y Patentoitavuuden kannalta merkittävä julkaisu, kun otetaan huomioon tämä ja yksi tai useampi samaan kategoriaan kuuluva julkaisu A Yleistä tekniikan tasoa edustava julkaisu, ei kuitenkaan patentoitavuuden este</p>		
Päiväys	Tutkija	
15.6.2000	J. Saranka	

(19) World Intellectual Property Organization
International Bureau




(43) International Publication Date
4 January 2001 (04.01.2001)

PCT

(10) International Publication Number
WO 01/01718 A1

- (51) International Patent Classification⁷: **H04Q 7/38**
- (21) International Application Number: **PCT/FI00/00357**
- (22) International Filing Date: **26 April 2000 (26.04.2000)**
- (25) Filing Language: **English**
- (26) Publication Language: **English**
- (30) Priority Data:
991466 28 June 1999 (28.06.1999) **FI**
- (71) Applicant (for all designated States except US): **NOKIA NETWORKS OY [FI/FI]**; Keilalahdentie 4, FIN-02150 Espoo (FI).
- (72) Inventors; and
- (75) Inventors/Applicants (for US only): **RAJANIEMI, Jaakko [FI/FI]**; Lapinrinne 2 A 11, FIN-00180 Helsinki (FI). **AHMAVAARA, Kalle [FI/FI]**; Hakaniemenranta 18 D 62, FIN-00530 Helsinki (FI). **EINOLA, Heikki [FI/FI]**; Kaksoiskiventie 7-9 B 5, FIN-02760 Espoo (FI). **BÄCK, Juha [FI/FI]**; Kulosaarenpuistotie 44 B 22, FIN-00570 Helsinki (FI). **HULKKONEN, Tony [FI/FI]**; Porvoonkatu 1 F 214, FIN-00510 Helsinki (FI). **HAUMONT, Serge [FR/FI]**; Riistavuorenkuja 3 B 10, FIN-00320 Helsinki (FI).
- (74) Agent: **KOLSTER OY AB**; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).
- (81) Designated States (*national*): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.
- (84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).
- Published:**
— With international search report.
- For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: LOCATION MANAGEMENT FOR CELLULAR SYSTEMS



(57) Abstract: A method for indicating a mobile station's (MS) location. A first radio network controller, RNC, acts as the mobile station's serving RNC (SRNC), for reporting the mobile station's location to the core network (CN). A second RNC acts as the mobile station's drift RNC (DRNC), for maintaining a radio connection with the mobile station. In response to fulfilment of at least one criterion in a first set of criteria, the mobile station (MS) sends location information about its location to the second RNC (DRNC) which forwards the location information to the first RNC (SRNC) for reporting to the core network (CN). There is also a second set of criteria for transforming the location information. In response to fulfilment of at least one criterion in the second set, the first RNC (SRNC) sends falsified information about the mobile station's location to the core network (CN).

Location management for cellular systems

Background of the invention

The invention relates to methods and equipment for reporting a mobile terminal's location. The invention can be used e.g. for implementing
5 handover in a mobile communications system. The invention is particularly useful in a system which is at least partly a third generation (3G) mobile communications system. 3G mobile communications systems, such as the UMTS (Universal Mobile Telecommunications System) are being standardised by the UMTS Forum and the European Telecommunication Standard Institute ETSI.
10 The current vision is that 3G systems will include both circuit-switched and packet-switched components.

Fig. 1 is a block diagram of a telecommunications system showing the components which are essential for understanding the invention. A UMTS Mobile Station MS consists of Mobile Equipment ME and a USIM card (User
15 and Services and Identity Module). There is a radio interface Uu between the MS and a Radio Access Network RAN, which comprises Base Stations BS under control of Radio Network Controllers RNC. For circuit-switched services, the RNCs are connected, via an Iu interface, to Mobile services Switching Centres MSC, and for packet-switched services, there is a connection, via a
20 Gb interface, to Serving GPRS Support Nodes SGSN (GPRS = General Packet Radio Service). The MSC and SGSN elements may include separate UMTS addition sections. Subscriber data related to the MS is stored permanently in a Home Location Register HLR and for circuit-switched operation, the data is transferred to the Visitor Location Register VLR of the MSC which currently
25 serves the MS. There may be separate Interworking units IWU for adapting the A and Gb interfaces of GSM/GPRS systems to the Iu interface of the UMTS. For storing equipment-related data, the network comprises an Equipment Identity Register EIR. For entering and updating subscriber-specific data, there is an Operation and Maintenance O&M section having a Man-
30 Machine Interface MMI. For creating and managing supplementary services, there is typically a dedicated Service Control Node SCN which can be seen as an evolved version of a Service Control Point (SCP) of Intelligent Networks.

Only the packet-switched section will be described in more detail, and it is assumed that this section will resemble a GPRS system. The GPRS
35 infrastructure comprises support nodes such as a GPRS gateway support node (GGSN) and a GPRS serving support node (SGSN). The main functions

of the GGSN nodes involve interaction with the external data network. The GGSN updates the location directory using routing information supplied by the SGSNs about an MS's path and routes the external data network protocol packet encapsulated over the GPRS backbone to the SGSN currently serving the MS. It also decapsulates and forwards external data network packets to the appropriate data network and handles the billing of data traffic.

The main functions of the SGSN are to detect new GPRS mobile stations in its service area, handle the process of registering the new MSs along with the GPRS registers, send/receive data packets to/from the GPRS MS, and keep a record of the location of the MSs inside of its service area. The subscription information is stored in a GPRS register (HLR) where the mapping between a mobile's identity (such as MS-ISDN or IMSI) and the PSPDN address is stored. The GPRS register acts as a database from which the SGSNs can ask whether a new MS in its area is allowed to join the GPRS network.

The GPRS gateway support nodes GGSN connect an operator's GPRS network to external systems, such as other operators' GPRS systems, data networks 11, such as an IP network (Internet) or a X.25 network, and service centres. Fixed hosts 14 can be connected to the data network 11 e.g. by means of a local area network LAN and a router 15. A border gateway BG provides access to an inter-operator GPRS backbone network 12. The GGSN may also be connected directly to a private corporate network or a host. The GGSN includes GPRS subscribers' PDP (Packet Data Protocol) addresses and routing information, i.e. SGSN addresses. Routing information is used for tunnelling protocol data units PDU from data network 11 to the current switching point of the MS, i.e. to the serving SGSN. The functionalities of the SGSN and GGSN can be connected to the same physical node.

The home location register HLR of the GSM network contains GPRS subscriber data and routing information and it maps the subscriber's IMSI into an SGSN address and one or more pairs of the PDP type and PDP address. The HLR also maps each PDP type and PDP address pair into a GGSN node. The SGSN has a Gr interface to the HLR (a direct signalling connection or via an internal backbone network 13). The HLR of a roaming MS and its serving SGSN may be in different mobile communication networks.

The intra-operator backbone network 13, which interconnects an operator's SGSN and GGSN equipment, can be implemented, for example, by

means of a local network, such as an IP network. It should be noted that an operator's GPRS network can also be implemented without the intra-operator backbone network, e.g. by providing all features in one computer.

Fig. 2 shows the protocol stacks used at various points in a 3G network.

A mobile station (MS) engaged in GPRS traffic sends a CELL UPDATE (CU) message after detecting that it has changed its cell. A number of cells constitute a routing area (RA), and when the routing area changes, the MS sends a ROUTING AREA UPDATE (RAU) message. In the UMTS the cell update messages are not sent to the SGSN, only to the RNC. Therefore the SGSN is not aware of the exact cell of the MS. For an active MS, the SGSN only knows an identifier of the RNC which handles the MS. For an idle MS, the SGSN only knows the MS's routing area identifier.

A first problem underlying the invention will now be described with reference to Fig. 3. A 3G system may pose certain problems which do not exist in 2G systems, such as the GSM and the GPRS. For example, when the MS is changing its cell, it is possible that a connection-oriented connection is not handled by the RNC controlling the MS's active cells but by another RNC. The former RNC is called a 'drift RNC' and the latter RNC is called a 'serving RNC'. In Fig. 3, RNC1 is the serving RNC (SRNC) and RNC2 is the drift RNC (DRNC). In such a case, the CU and RAU messages are transmitted over the air interface piggybacked to the channel which is reserved for the circuit-switched connection (connection-oriented connection), and they terminate at the serving RNC. In a GPRS core network, if the Radio Access Network (RAN) inserts a cell ID (identifier) into the CU or RAU messages, thereby indicating where the MS is actually located, and if that cell is not controlled by the serving RNC, the SGSN may use another RNC for the packet-switched connections. This is not possible, however, because all simultaneous connections for one user should be handled by one RNC. In other words, there may be an ambiguity concerning the RNC which the SGSN should use. The same holds in a UMTS system if the Radio Access Network (RAN) inserts a cell ID (identifier) into a RAU message or an equivalent.

A second, related problem is that current GPRS or 3G systems do not offer a smooth Inter-SGSN routing area update (RAU) procedure. A lot of signalling is needed between the new SGSN and the old SGSN, the HLR, MSC and the GGSN(s). In particular, the new SGSN must receive the sub-

scriber data from the old SGSN before it can be sure that it can accept the RAU and continue signalling. This signalling causes a delay of up to several seconds, which in some cases could be unacceptable. Moreover, in packet traffic a virtual connection can last for several days. Therefore, the existing
5 concepts of an anchor-MSC and float-MSC are not appropriate.

Disclosure of the invention

It is an object of the invention to provide a method and equipment for eliminating the first problem associated with prior art systems. The object is attained with the method and equipment which are characterized by what is
10 disclosed in the characterizing part of the appended independent claims. Solutions to the second problem and preferred solutions to the first problem are disclosed in the appended dependent claims.

The invention is based on the idea that for a terminal sending information on the basis of which its location can be determined (such as a mobile station having a connection-oriented connection while sending a CU or
15 RAU message), the terminal's location information (e.g. its cell ID) can be transformed, e.g. by using a masked or falsified (faked) location information, such as a fake cell ID. The fake location information is preferably chosen so that the SGSN assumes the location of the MS to be under the serving RNC.
20 A certain pool or group of cell addresses can be used for this purpose. It might be beneficial to choose the addresses so that the SRNC (or SGSN) can detect that the traffic has been forwarded.

According to various preferred embodiments of the invention, the information about the MS's location indicates one or more of the following:

25 a location (e.g. a cell) which is controlled by the SRNC and which is part of the MS's active set, if such a cell exists;

a virtual location (e.g. cell), which is not controlled by either RNC, in case the MS's active set does not comprise a cell which is controlled by the SRNC;

30 the last location (e.g. a cell) which is controlled by the SRNC and which has been part of the MS's active set in case the MS's active set does not comprise a cell which is controlled by the SRNC;

a location (e.g. a cell) controlled by the DRNC in case the MS's active set does not comprise a cell controlled by the SRNC; and/or

35 a location (e.g. a cell) whose location information the MS received last.

The fact that the MS's location information indicates one of these cells has two possible interpretations. The MS's location information may indicate such a cell either explicitly or implicitly. An explicit indication means that the location information contains actual cell identifiers. An implicit indication
5 means that the location information contains some information (e.g. one or more routing or location area identifiers) on the basis of which a cell can be identified (if so desired). It is also feasible to transfer only some location-related data and use it for calculating the MS's location.

The criteria for sending location information preferably comprises a
10 change of the MS's location, activation of a PDP context for the MS and expiry of a recurring period of time.

As briefly noted above, the information about the MS's location may indicate a location, such as a cell, whose location information the MS received last. When a mobile station has at least one active connection, it receives
15 system information only via its dedicated signalling connection. This system information comprises e.g. current location (such as routing area, location area and cell identity) of the mobile station. The system information is similar in nature to the information which the MS receives via a broadcast control channel BCCH when it does not have any active connections. The SRNC only sends
20 system information about the cells controlled by it. In other words, it does not send system information about cells controlled by the DRNC. Based on the system information, the MS can determine whether or not it has moved into a new routing or location area. The SRNC sends this information as necessary. One suitable criterion for sending it is that the MS has moved and its active set
25 does not contain the cell whose system information the SRNC has sent last, or after an SRNC handover (relocation).

Use of the transformed location, such as a fake cell ID, causes another problem, however. When the MS's last connection-oriented connection is terminated and the serving RNC deleted from the MS-URAN connection, the
30 SGSN must be informed about the new (correct) RNC. This holds also for cases where the serving RNC is changed. This problem can be solved as follows. If the MS's last connection-oriented connection is terminated or if the serving RNC is changed, an additional CU or RAU must be performed for the MS, even if the MS's location information has not changed.

35 The location reporting functionality performed by a serving RNC can be summarised as follows:

1. Check if RNC handover should be performed. If not, then:
2. Select a location, such as a cell which is controlled by the serving RNC and which is part of the MS's active set, if such a cell exists. (N.B. The active set must also comprise at least one cell controlled by the drift RNC, otherwise the concept of drift RNC would not exist.)

If no handover was performed in step 1 or no cell was found in step 2, then do one of the following:

- 3A. Select a virtual location, such as a cell. A virtual cell is not a real cell (i.e. it is not covered by radio transceivers); or
- 3B. Select, among the cells controlled by the serving RNC, the last one used by the MS.

If step 3A is taken, i.e. a virtual location is selected, the core network elements (the MSC and/or the SGSN) must determine that the location information does not refer to reallocation. Such a determination can be made on the basis of a suitable cell ID numbering plan or a translation table.

Brief description of the drawings

The invention will now be described in connection with its preferred embodiments, with reference to the accompanying drawings, in which:

Fig. 1 is a block diagram of a telecommunications system showing the components which are essential for understanding the invention;

Fig. 2 shows the protocol stacks used at various points in a 3G network;

Fig. 3 is a simplified block diagram for pointing out the problem more clearly;

Fig. 4 shows a routing area update (RAU) procedure for a GPRS network; and

Fig. 5 shows an alternative Inter-SGSN routing area update procedure according to a preferred embodiment of the invention.

Detailed description of the invention

Fig. 4 shows a routing area update (RAU) procedure for a GPRS network. In step 4-1 the MS sends a ROUTING AREA UPDATE REQUEST via RNC2 (drift RNC) to RNC1 (serving RNC). In step 4-2 RNC1 adds the MS's location information and forwards the RAU Request to SGSN1. In step 4-3 SGSN2 requests the MS's PDP context from SGSN1 which responds in step 4-4. In step 4-5 SGSN1 begins to forward MS-terminated (MT) packets to

SGSN2. Security functions have been shown as step 4-6. In step 4-7 SGSN2 sends an UPDATE PDP CONTEXT REQUEST to the GGSN node which responds in step 4-8. In step 4-9 the MS's location is updated in the HLR. In step 4-10 the HLR cancels the MS's location in SGSN1 which acknowledges this in step 5 4-11. In step 4-12 the HLR sends an INSERT SUBSCRIBER DATA to SGSN2 which acknowledges in step 4-13. In step 4-14 the HLR sends to SGSN2 an acknowledgement to the message sent in step 4-9. In step 4-15, if the MS is IMSI-attached and does not have a circuit-switched connection, the SGSN-VLR association must be updated. SGSN2 updates the MS's location and 10 SGSN number in the VLR, which acknowledges these in step 4-16. In steps 4-17 and 4-18 the RAU process is completed.

Fig. 5 shows an alternative Inter-SGSN routing area update procedure according to a preferred embodiment of the invention. This embodiment and its alternative modifications solve the second problem underlying the invention. 15

Due to macrodiversity, the triggering of a RAU is less clear than in 2G systems. A RAU could be triggered e.g. if all cells in the MS's active set belong to the new RA, or if more than half of the cells belong to it. In step 5-1 the MS sends a ROUTING AREA UPDATE REQUEST via RNC2 (drift RNC) to 20 RNC1 (serving RNC). The MS sends the RAU request via its uplink connection, if one exists. Because of the coexistence of the drift RNC and the serving RNC, the update is received by the SRNC which does not control the MS's new routing area. The MS should suspend its session management procedures. In step 5-2 RNC1 adds the MS's location information and forwards the 25 RAU REQUEST to SGSN1. This is in contrast to prior art GPRS systems where the RAU REQUEST is sent to SGSN2. In step 5-3 security functions may be performed, as usual. A benefit of sending the RAU REQUEST to SGSN1 is that SGSN1 already knows the MS's digital signature (PTMSI signature in GPRS terms), and it is likely to have authentication triplets for it. Thus there is no 30 need to fetch these separately, whereby the delays due to the inter-SGSN handover can be shortened.

In step 5-4, if the security functions are completed successfully, the SGSN1 sends a FORWARD RAU REQUEST to SGSN2. This message includes parameters for resuming the connection(s) after the RAU. Such parameters 35 include session management data and eventually lu information (address of

RNC2). SGSN1 may start a timing period during which it will keep the MS's data in its memory.

In step 5-5 SGSN2 updates the MS's location (IMSI, SGSN address) in the HLR. In step 5-6 the HLR inserts the subscriber data (IMSI, subscription details) into SGSN2 which validates the MS's presence in the new RA. If all regional and other checks are passed, SGSN2 establishes an MM (Mobility Management) context for the MS and returns an acknowledgement to the HLR in step 5-7.

In step 5-8 SGSN2 may establish an lu link to RNC2 which may send some radio parameters to resume quickly a connection with the MS. This feature is especially useful if the MS has a delay-sensitive application (this can be determined by checking the MS's session management context).

In step 5-9 SGSN2 returns an accept message to the message sent in step 5-4. The accept message includes the new RA index, the MS's new temporary identity (P-TMSI in GPRS terms) and/or its new digital signature. Additionally, some radio parameters or codes obtained from RNC2 may be sent. SGSN1 should immediately acknowledge this message to facilitate error handling. In step 5-10 SGSN1 sends to the MS an RAU ACCEPT message which preferably contains the same parameters as the message of step 5-9. Additionally, if an acknowledgement transmission is active, it may contain some protocol state information known by SGSN1 (this corresponds to LLC acknowledgement in GPRS).

In step 5-11 SGSN1 suspends downlink data transmission for acknowledged mode, in order to keep the protocol state intact. Depending on the QoS, SGSN1 may continue data transmission for unacknowledged mode.

In step 5-12 the MS acknowledges with a RAU COMPLETE message which contains the new temporary identity (P-TMSI) and some protocol state information known by the MS, such as an LLC acknowledgement for each LLC connection used by the MS (which confirms all MT N-PDUs transferred successfully before the start of the update procedure. If the packet acknowledgement (equivalent to LLC acknowledgement in GPRS) confirms reception of certain N-PDUs, these N-PDUs will be discarded by SGSN1. This message will trigger RNC relocation (which in this embodiment is triggered by the MS).

In step 5-13 the MS establishes a radio connection with RNC2. If radio parameters were sent in step 5-10 (RAU ACCEPT), the MS could set up a radio connection immediately with these parameters. Otherwise, the MS

should re-establish the radio connection by accessing the common channel, which causes a longer break in the connection. This is why sending the radio parameters in step 5-10 may be QoS-dependent. The MS should send an uplink packet (not shown) to SGSN2 in case the RAU COMPLETE message was
5 lost because of error handling. An alternative embodiment, omitting step 5-13, will be described later.

In step 5-14 SGSN1 sends a FORWARD RAU COMPLETE message to SGSN2. In step 5-15 SGSN1 cancels the lu links towards RNC1 and begins to forward downlink packets to SGSN2. It may keep the MS's context and for-
10 ward MT packets until the expiry of the optional timing period which was started in step 5-4. In step 5-16, when SGSN2 receives the FORWARD RAU COMPLETE message, it resumes data transmission towards the MS.

In step 5-17 SGSN2 sends to the relevant GGSN(s) an UPDATE PDP CONTEXT REQUEST (SGSN2 address, Tunnel Identifier, QoS Negotiated).
15 The GGSNs update their PDP context fields and return a response in step 5-18. N.B: Steps 5-17 and 5-18 may take place any time after step 5-5.

In step 5-19 the HLR cancels the MS's location in SGSN1. This message contains the MS's IMSI, and the cancellation type is set to Update procedure. If the optional timer was not set in step 5-4, SGSN1 deletes the
20 MS's MM and PDP contexts. Otherwise it waits until the timer expires. The timing period allows SGSN1 to complete forwarding of N-PDUs. It also ensures that the MS's MM and PDP contexts are kept in case the MS initiates another Inter-SGSN RAU before completing the ongoing RAU. In step 5-20 SGSN1 acknowledges with a CANCEL LOCATION ACK.

25 According to an alternative embodiment step 5-13 is omitted. Instead, during step 5-15 RNC1 receives an indication from SGSN1 that the RNC could now be relocated. RNC1 will inform RNC2 which will start handling the MS directly.

In general, the invention is equally applicable if the SGSN is re-
30 placed by a 3G MSC (or an MSC/SGSN combination). For this embodiment, the MSC and/or SGSN could be called 'switching elements' since they route packets and/or establish circuit-switched connections.

In GSM systems no location area updates are performed during connection, in order not to confuse the relay and anchor MSCs. With macro
35 diversity the LAU could reach the old MSC directly, whereby it is possible to have a LAU during a call. However, in a hard inter-MSC handover, a special

message (LAU with an active call indication) may be needed. Such a message could trigger the new MSC to establish a connection with the old MSC and try to resume the call. A problem is that this would happen especially between the GSM and the UMTS, which means that a GSM MSC would need to interpret
5 this special LAU message.

It should be noted that figures 4 and 5 illustrate worst-case scenarios in the sense that both RNCs are under different SGSN nodes or MSCs. If the SGSNs or the MSCs are the same, these scenarios could be simplified accordingly.

Claims

1. A method for indicating a terminal's (MS) location in a telecommunications system comprising:

a core network (CN); and

5 an access network (RAN) comprising a first network controller, which at least temporarily acts as the terminal's serving network controller (SRNC), for reporting the terminal's location to the core network, and a second network controller, which at least temporarily acts as the terminal's drift network controller (DRNC), for maintaining a connection with the terminal;
10 wherein

there is a first set of predetermined criteria for sending information about the terminal's (MS) location to the core network (CN); and

in response to fulfilment of at least one criterion in the first set, the terminal (MS) sends to the second network controller (DRNC) location information (4-1, 5-1) on the basis of which the terminal's location can be determined; and the second network controller (DRNC) forwards the location information to the first network controller (SRNC) for reporting to the core network (CN);
15

characterized in that

20 there is a second set of at least one predetermined criterion for transforming the location information;

the first network controller (SRNC) checks whether at least one criterion in the second set is fulfilled; and

in response to fulfilment of at least one criterion in the second set,
25 the first network controller (SRNC) sends transformed information (4-2, 5-2) about the terminal's location to the core network (CN).

2. A method according to claim 1, characterized in that in response to terminating the last connection-oriented connection with the terminal, the first network controller (SRNC) reports the terminal's correct location
30 to the core network (CN).

3. A method according to claim 1 or 2, characterized in that the information about the terminal's (MS) location indicates a location which is controlled by the first network controller (SRNC) and which is part of the terminal's active set, if such a location exists.

4. A method according to claim 3, characterized in that if the terminal's active set does not comprise a location which is controlled by the first network controller (SRNC), the information about the terminal's (MS) location indicates a virtual location, which is not controlled by either of said network controllers.

5. A method according to claim 3, characterized in that if the terminal's active set does not comprise a location which is controlled by the first network controller (SRNC), the information about the terminal's (MS) location indicates the last location which is controlled by the first network controller and which has been part of the terminal's active set.

6. A method according to claim 3, characterized in that if the terminal's active set does not comprise a location which is controlled by the first network controller (SRNC), said information about the terminal's (MS) location indicates a location which is at least partially controlled by the first network controller.

7. A method according to any one of the preceding claims, characterized in that the information about the terminal's (MS) location indicates a location the location information of which the terminal received last.

8. A method according to any one of the preceding claims, characterized in that if the terminal's (MS) active set does not comprise a location controlled by the first network controller (SRNC), the information about the terminal's (MS) location indicates a location controlled by the second network controller (DRNC).

9. A method according to any one of the preceding claims, characterized in that said information about the terminal's (MS) location indicates at least one cell identifier, routing area identifier or location area identifier.

10. A method according to any one of the preceding claims, characterized in that said first set of criteria comprises a change of the terminal's location, activation of a PDP context for the terminal and expiry of a recurring period of time.

11. A method according to any one of the preceding claims, characterized in that

the first and the second network controller (RNC1, RNC2) are associated, respectively, with a first and a second switching element (SGSN1, SGSN2) for maintaining subscription information related to the terminal (MS);
5 and

information about the terminal's location is received by the first switching element (SGSN1) sends (5-4) information about the terminal's location to the second switching element (SGSN2) without a separate request.

10 12. A method according to claim 11, characterized in that said information about the terminal's location comprises the terminal's Packet Data Protocol and/or Mobility Management context.

13. A method according to claim 11 or 12, characterized in that each of the first and the second switching element (SGSN1, SGSN2) is
15 substantially an SGSN node, a Mobile services Switching Centre or a combination of both.

14. A method according to any one of the preceding claims, characterized in that said terminal is a mobile station, said access network is a radio access network and said network controller is a radio network controller.
20

15. A first network controller for supporting a terminal (MS) in a telecommunications system which comprises a core network (CN) and an access network (RAN);

wherein said first network controller is adapted to act, at least temporarily, as the terminal's serving network controller (SRNC) in said access network (RAN), for reporting the terminal's location to the core network (CN);
25 and

the first network controller (SRNC) is adapted to receive location information from a drift network controller (DRNC) and to report it to the core network (CN) for determining the terminal's (MS) location;
30

characterized in that

the first network controller (SRNC) is adapted to transform said information about the terminal's location before reporting it to the core network (CN).

Fig. 1





Fig. 2



*WCDMA in 3G

Fig. 3






Fig. 4





INTERNATIONAL SEARCH REPORT

International application No.

PCT/FI 00/00357

A. CLASSIFICATION OF SUBJECT MATTER

IPC7: H04Q 7/38

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC7: H04Q

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

SE,DK,FI,NO classes as above

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P,X	WO 9966740 A2 (EINOLA), 23 December 1999 (23.12.99), page 3, line 7 - page 7, line 24	15
P,A	--	1-14
P,A	WO 0011878 A2 (TELEFONAKTIEBOLAGET LM ERICSSON (PUBL)), 2 March 2000 (02.03.00), page 6, line 18 - page 8, line 13	1-15
A	WO 9920071 A1 (TELEFONAKTIEBOLAGET LM ERICSSON (PUBL)), 22 April 1999 (22.04.99), page 5, line 6 - page 7, line 3, abstract	1-15
	-- -----	



Further documents are listed in the continuation of Box C.



See patent family annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance: the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance: the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search

13 October 2000

Date of mailing of the international search report

17-10-2000

Name and mailing address of the ISA/

Swedish Patent Office

Box 5055, S-102 42 STOCKHOLM

Facsimile No. +46 8 666 02 86

Authorized officer

Jaana Raivio/mj

Telephone No. +46 8 782 25 00

INTERNATIONAL SEARCH REPORT
Information on patent family members

01/08/00

International application No.

PCT/FI 00/00357

Patent document cited in search report				Publication date		Patent family member(s)		Publication date	
WO	9966740	A2	23/12/99	AU	4554499	A	05/01/00		
				AU	5900699	A	21/03/00		
				EP	1025668	A	09/08/00		
				WO	0012593	A	09/03/00		
WO	0011878	A2	02/03/00	AU	5664599	A	14/03/00		
WO	9920071	A1	22/04/99	AU	9468798	A	03/05/99		
				SE	9703697	A	11/04/99		